BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Dasarahalli Division

(15)

D.T.S

NAME OF WORK:- Providing chambers to existing borewell and consealing to road surface area in ward no 12 shettihalli sub - division

S No	Item Name	Unit	Quantity	Rate In Figure in Rs	
				In Figures	in words
1	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. (PWD SR 2018-19 P.No: 6, I.No.: 2.4)	Cum	105.48		
2	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (PWD,SZB,SR,2018-19. Pg No -13, I. No-4.3)	Cum	8.10		
3	KSRB 4.2.1 : Providing and laying in position reinforced cement concrete of Design mix M25 with OPC cement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (PW,P& IWTD SR 2018-19, Pg No 14, Item No. 4.10)	Cum	43.09		

S No	Item Name	Unit	Quantity	Rate In Figure in Rs	
				In Figures	in words
4	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 550 (PWD,SZB,SR,2018-19, P-18, I-4.46.3)	MT	3.02		
5	KSRB 4.6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (PWD,SZB,SR,2018-19, P-16, I-4.31)	Sqm	233.28		
6	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) - 50mm nominal OD pipes (PWD,SZB,SR,2018-19, P-98, I-13.85.6)	Rmt	240.00		
7	Providing and laying 25cm thick Pre Cast Cover slabs including cost of all materials, labours, curing, transportation, loding unloding etc.., complete as per the direction of Engineer in charge.	Sqm	54.00		

Number of corrections

DTS Approved

Executive Engineer
Dasarahalli Division